REDWOOD SANITARY SEWER SERVICE DISTRICT
JOSEPHINE COUNTY

ENGINEERING REPORT

Prepared for:

City of Grants Pass
101 Northwest A Street
Grants Pass, Oregon 97526

and

Josephine County
201 River Heights Way
Grants Pass, Oregon 97527

Prepared by:

Parametrix, Inc.
700 NE Multnomah
Suite 1160
Portland, OR 97232

PMX #27-2192-05
April 1999
(Revised November 1999)

CERTIFICATE OF ENGINEER

The technical material and data contained in this document were prepared under the supervision and direction of the undersigned, whose seal, as a professional engineer licensed to practice as such, is affixed below.

Prepared by: Allan Maas, P.E.

Checked by: Tom Nielsen, P.E.

Approved by: Steven C. Gilbert, P.E.

TABLE OF CONTENTS

Page

EXECUTIVE SUMMARY ES-1

1. INTRODUCTION 1-1
   1.1 BACKGROUND 1-1
   1.2 AUTHORITY AND PURPOSE 1-3
   1.3 PREVIOUS STUDIES AND REPORTS 1-4
   1.4 ACKNOWLEDGMENTS 1-5

2. SERVICE AREA 2-1
   2.1 INTRODUCTION 2-1
   2.2 DESCRIPTION OF AREA 2-1
   2.3 TOPOGRAPHY 2-1
   2.4 PRECIPITATION 2-3
   2.5 GRANTS PASS IRRIGATION DISTRICT 2-3
   2.6 LAND USE 2-5
   2.7 EXISTING POPULATION 2-5
   2.8 POPULATION PROJECTIONS 2-5

3. EXISTING WASTEWATER COLLECTION SYSTEM 3-1
   3.1 DESCRIPTION OF FACILITIES 3-1
   3.2 MOST RECENT FLOW MONITORING 3-1
   3.3 INFILTRATION AND INFLOW ASSESSMENT 3-8
      3.3.1 Infiltration 3-8
      3.3.2 Inflow 3-9
   3.4 COLLECTION SYSTEM CONDITIONS 3-9
      3.4.1 Non-Excessive I&I Definition 3-9
      3.4.2 Comparison to Measured Flows 3-11
   3.5 INFILTRATION AND INFLOW RECOMMENDATION 3-12
      3.5.1 Cost 3-12

4. EXISTING WASTEWATER TREATMENT SYSTEM 4-1
   4.1 EXISTING WASTEWATER TREATMENT PLANT 4-1
      4.1.1 Description of Facilities 4-1
   4.2 WASTEWATER FLOW AND LOAD 4-4
      4.2.1 Existing Wastewater Flow 4-5
      4.2.2 Existing Wastewater Load 4-5
   4.3 PLANT REGULATORY LIMITATIONS 4-7

TABLE OF CONTENTS (continued)

Page

INTRODUCTION TO CHAPTER 5 - FUTURE TREATMENT REQUIREMENTS . . 5-1A

5. FUTURE TREATMENT REQUIREMENTS 5-1
- 5.1 WASTEWATER FLOW AND LOAD PROJECTIONS 5-1
  - 5.1.1 Flow Projections 5-1
  - 5.1.2 Impact of Water Conservation 5-2
  - 5.1.3 Load Projections 5-4
- 5.2 REGULATORY TREATMENT CRITERIA 5-5
  - 5.2.1 OAR 340-41-375 5-5
  - 5.2.2 OAR 340-41-026 5-6
- 5.3 RECEIVING WATER QUALITY CRITERIA 5-7
  - 5.3.1 Introduction 5-7
  - 5.3.2 Discharge Description 5-8
  - 5.3.3 Receiving Water Conditions 5-8
  - 5.3.4 Water Quality Standards 5-13
  - 5.3.5 Mixing Zone Evaluation 5-16
  - 5.3.6 Effluent Quality 5-23
  - 5.3.7 Water Quality Analysis 5-25
  - 5.3.8 Recommendations 5-34
- 5.4 FUTURE TREATMENT REQUIREMENTS 5-35

6. TREATMENT ALTERNATIVES 6-1
- 6.1 ALTERNATIVES INVESTIGATED 6-1
- 6.2 ALTERNATIVES 1, 2, AND 3 6-2
- 6.3 ALTERNATIVES 4 AND 5 6-9
- 6.4 NEW BIOSOLIDS TREATMENT PLAN 6-13
  - 6.4.1 Anaerobic Digestion Process Description 6-13
  - 6.4.2 Preliminary Design Criteria 6-17
  - 6.4.3 Site Plan 6-18
  - 6.4.4 Capital and Operations and Maintenance Costs 6-18
  - 6.4.5 Preliminary Screening of Alternatives 1 Through 5 6-18
- 6.5 ALTERNATIVES 6 THROUGH 12 6-21
  - 6.5.1 Design Criteria 6-22
  - 6.5.2 Description of Alternatives 5 Through 12 6-25
  - 6.5.3 Cost Estimates 6-31
  - 6.5.4 Preliminary Screening of Alternatives 6 Through 12 6-31
- 6.6 PREFERRED ALTERNATIVE SELECTION 6-32
- 6.7 ENVIRONMENTAL REVIEW 6-36
  - 6.7.1 Introduction 6-36
  - 6.7.2 Zoning and Land Uses 6-37

TABLE OF CONTENTS (continued)

Page

6.7.3 Historic and Cultural Resources 6-37
6.7.4 Economic Considerations 6-38

6.7.5 Wetlands 6-38
6.7.6 Floodplains 6-39
6.7.7 Agricultural Lands 6-39
6.7.8 Wild and Scenic Rivers 6-40
6.7.9 Fish and Wildlife 6-40
6.7.10 Threatened and Endangered Species 6-40
6.7.11 Other Unique or Sensitive Environmental Resources 6-40
6.8 CONSTRUCTION TECHNIQUES, BEST MANAGEMENT PRACTICES, AND MITIGATION OF SELECTED NATURAL RESOURCE CONCERNS 6-41
6.8.1 Construction Techniques 6-41
6.8.2 Best Management Practices 6-42
6.8.3 Mitigation of Selected Natural Resource Concerns 6-42
6.9 PUBLIC PARTICIPATION 6-42
6.10 WASTEWATER FACILITIES PLAN UPDATE 6-43
6.10.1 District Board Briefing - November 18, 1998 6-43
6.10.2 Public Meeting/Forum - November 19, 1998 6-44
6.10.3 District Board Briefing - December 10, 1998 6-44
6.10.4 District Board Briefing, Preferred Alternative Selected - December 14, 1998 6-44
6.10.5 District Board Briefing - March 8, 1999 6-44
6.10.6 District Board Adopts Wastewater Facilities Plan Update - April 28, 1999 6-44
6.11 PREFERRED ALTERNATIVE IMPLEMENTATION 6-44
6.11.1 Project Press Release and District-wide Project Update 6-44
6.11.2 Letter to Affected Property Owners 6-45
6.11.3 Affected Property Owner Meeting 6-45
6.11.4 Conveyance Route Field Walk 6-45
6.11.5 Property Owner Update/Meeting Announcement and Property Owner Meeting 6-45
6.11.6 Individual Property Owner Meetings 6-45
6.12 FUTURE PUBLIC INVOLVEMENT ACTIVITIES 6-46

7. PREFERRED ALTERNATIVE 7-1
7.1 PUMP STATION DESIGN CRITERIA 7-1
7.1.1 RI-25 Pump Station 7-1
7.1.2 RI-0 Pump Station 7-2

Page

7.2 FORCE MAIN DESIGN 7-2
7.2.1 RI-25 Pump Station Force Main 7-2
7.2.2 RI-0 Pump Station Force Main 7-3
7.3 RELATED ISSUES 7-4
7.4 PROJECT SCHEDULE 7-6
7.4.1 Operation During Construction 7-7

8. FINANCING PLAN 8-1
8.1 BACKGROUND 8-1
8.2 EXISTING FINANCES 8-1
8.3 SYSTEM DEVELOPMENT CHARGES 8-3
8.4 FUNDING ALTERNATIVES 8-4
8.5 FINANCING ALTERNATIVES 8-4
8.5.1 Base Case Scenario 8-4
8.5.2 Alternative One Scenario 8-4
8.6 PROJECT FUNDING SUMMARY 8-5

APPENDICES

APPENDIX A – NPDES PERMIT
APPENDIX B – POPULATION INFORMATION
APPENDIX C – REDWOOD WWTP DAILY MONITOR DATA
APPENDIX D – 1994 CAPACITY ANALYSIS
APPENDIX E – 1994 WASTEWATER FLOW ANALYSIS
APPENDIX F – OUTFALL MIXING ANALYSIS, DRAWING, AND DATA
APPENDIX G – WWTP ALTERNATIVE COST ESTIMATES
APPENDIX H – CONVEYANCE ALTERNATIVES COST ESTIMATES
APPENDIX I - PUBLIC PARTICIPATION
APPENDIX J – CONVEYANCE PREDESIGN REPORT
APPENDIX K – PEDESTRIAN BRIDGE AND EXISTING PUMP STATION
APPENDIX L – FORCE MAIN CALCULATIONS
APPENDIX M – FINANCIAL EVALUATION CALCULATIONS

LIST OF FIGURES

		Page
1-1	Redwood Sanitary Sewer Service District and Grants Pass	1-2
2-1	Service Area	2-2
2-2	Yearly Average Precipitation	2-4
2-3	Monthly Average Precipitation	2-4
2-4	Redwood District Population Projections	2-6
3-1	Existing District Wastewater Collection System	3-2
3-2	Flow Monitoring Results - Manhole R1-48	3-5
3-3	Flow Monitoring Results - Manhole R1-26	3-6
3-4	Flow Monitoring Results - Manhole R1-5	3-7
3-5	Flow Monitoring Results and Rainfall Data - Manhole R1-5	3-10
4-1	Process Schematic and Site Plan	4-2
4-2	Redwood WWTP Average Daily Flow/Month	4-6
4-3	Redwood WWTP 30-Day Average BOD	4-6
5-1	Wastewater Flow Projections	5-3
5-2	Outfall and Vicinity, Redwood Sanitary Sewer Service District	5-9
5-3	Rogue River Cross Section at Outfall	5-11
5-4	Rogue River Dissolved Oxygen	5-28
5-5	Rogue River Temperature	5-32
6-1	Treatment Alternative 1 - Construct Stabilization with Anoxic Selectors	6-4
6-2	Treatment Alternative 2 - Sequencing Batch Reactor (SBR)	6-6
6-3	Treatment Alternative 3 - Add Biofilter Process	6-7
6-4	Treatment Alternative 4 - Complete Mix/Anoxic Selectors with Effluent Filtration	6-11
6-5	Treatment Alternative 5 - Sequencing Batch Reactor (SBR) with Effluent Filtration	6-12
6-6	Anaerobic Digestion Flow Schematic	6-14
6-7	Treatment Option Site Plan	6-19
6-8	Rogue River Crossing Cross Section	6-26
6-9	Treatment Alternatives 6 Through 12	6-29
6-10	Treatment Alternatives 7, 9A, 9B	6-33
7-1	Project Implement Schedule	7-8

LIST OF TABLES

		Page
ES-1	Wastewater Flow Projections, Year 2020	ES-2
ES-2	Redwood WWTP BOD and TSS Load (lbs/day)	ES-3
ES-3	Anticipated Future BOD and TSS Effluent Limitations Based on OAR 340-41-375	ES-3
ES-4	Anticipated Future BOD and TSS Effluent Limitations Based on OAR 340-41-026	ES-4
ES-5	Treatment Alternatives 1 through 5 - Estimate of Probable Costs (costs in $1,000s)	ES-5
ES-6	Treatment Alternatives 1 through 5 - Annual O&M Costs	ES-6
ES-7	Treatment Alternatives 6 through 12 - Estimate of Probable Cost	ES-7
ES-8	Treatment Alternatives 6 through 12 - Annual O&M Costs	ES-8
ES-9	Treatment Alternatives 1, 4, 7, 9A, and 9B - Present Worth Cost Estimates (in $1,000s)	ES-9
2-1	Historical Growth	2-7
3-1	As-built Components of the District's Existing Wastewater Collection System	3-1
3-2	Rainfall During Flow Monitoring Period (1992)	3-3
3-3	Rainfall During Flow Monitoring Period (1992-1993)	3-4
4-1	1998 Plant Flow Conditions	4-5
4-2	1998 Plant BOD Load Conditions (lbs/day)	4-5
4-3	1998 Plant TSS Load Conditions (lbs/day)	4-7
4-4	Existing Redwood WWTP NPDES Limits	4-7
5-1	Wastewater Flow Projects, Year 2020	5-1
5-2	Water Conservation Efforts vs. Sewer Flow	5-2
5-3	Redwood WWTP BOD and TSS Load (lbs/day)	5-4
5-4	Anticipated Future BOD and TSS Effluent Limitations Based on OAR 340-41-375	5-6
5-5	Anticipated Future BOD and TSS Effluent Limitations Based on OAR 340-41-026	5-6
5-6	Statistical Flow Summaries for Rogue River After Regulation of Lost Creek Lake (1978-1987)	5-10
5-7	River and Channel Characteristics	5-12
5-8	Ambient Water Quality Statistics for Rogue River Near Redwood Wastewater Treatment Plant	5-14
5-9	Near- and Far-Field Model Input Parameters	5-22
5-10	Mixing Model Results	5-23
5-11	Water Quality Analysis Summary	5-26
5-12	Compliance Summary	5-27
5-13	Monitoring Recommendations	5-34
6-1	Preliminary Sizing Criteria, New Unit Treatment Processes Treatment Plant Expansion Alternatives Meeting OAR 340-41-375	6-2
6-2	Preliminary Sizing Criteria, New Unit Treatment Processes Treatment Plant Expansion Alternatives Meeting OAR 340-41-026	6-9

LIST OF TABLES (continued)

		Page
6-3	Anaerobic Digestion Preliminary Design Criteria	6-17
6-4	Treatment Alternatives 1 through 5 Estimate of Probable Costs (costs in $1,000s)	6-20
6-5	Treatment Alternatives 1 through 5 Annual O&M Costs	6-21
6-6	Treatment Alternatives 6 through 12 Design Flows	6-22
6-7	Force Main Alternatives Preliminary Cost Estimates	6-31
6-8	Treatment Alternatives 1, 4, 7, 9A, and 9B Present Worth Cost Estimates ($1,000s)	6-32
6-9	Treatment Alternative Selection Evaluation Criteria and Selection Ranking	6-35
7-1	Transfer of BOD and TSS Wasteload Capacity (lbs/day)	7-5
8-1	General District Operating Revenue and Expenses	8-2
8-2	Base Case Scenario Total Project Funding Capability	8-4
8-3	Alternative One Scenario Total Project Funding Capability	8-5