

ADDENDUM NO. 1

to **CONTRACT DOCUMENTS** for

"C" Street Sanitary Sewer and Waterline Replacement
Project No. SE6156/WA4841
Grants Pass, Oregon 97526

To All Plan Holders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction "C" Street Sanitary Sewer and Waterline Replacement; Project No. SE6156/WA4841, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

1. ON THE CONSTRUCTION PLANS...

- On Sheet 2 of 3, Legend Note No.13, Replace 70 L.F. **with 66 L.F.**
- On Sheet 2 of 3, Legend Note No.14, Replace 62 L.F. **with 52 L.F.**
- On Sheet 2 of 3, Legend Note No. 16 Replace CL.50 **with CL.52**
- On Sheet 2 of 3, Profile, Replace CL.50 **with CL.52**

2. IN THE CONTRACT DOCUMENTS...

- Bid Proposal, Bid Schedule Item No. 7, Change Quantity from 120 LF **to 52 LF**
- Bid Proposal, Bid Schedule, Add Item No. 7A:

7A	8" Sanitary Sewer Main, Class 52 Ductile Iron Pipe , per approved plans and APWA /ODOT Sec. 00445. Includes pipe, trench excavation, bedding, backfill and connection to existing main, per GPSD #107 and APWA/ODOT Sec. 00405, installed, complete.			
	<u>66</u>	<u>LF</u>	\$	\$

- Bid Proposal, Bid Schedule Item No. 8, Change Class 50 **to Class 52**
- Bid Proposal, Bid Schedule Item No. 8, Change Quantity from 2 **to 3**
- Bid Proposal, Bid Schedule Item No. 14, Change CL 54 **to Class 52**

ATTACHED ARE REVISED PAGES OF THE BID PROPOSAL. PLEASE USE THESE REPLACEMENT PAGES WHEN SUBMITTING YOUR BID. MANDATORY PRE-BID ATTENDANCE LIST IS ALSO ATTACHED.

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE

HEREBY AGREED TO THIS _____ DAY OF _____ 2013.

Bidder's Name (Company)

BY: _____
(Signature)

BID SCHEDULE
“C” Street Sanitary Sewer and Waterline Replacement
SE6156/WA4841

PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				
Item	Quantity	Unit	Unit Price (Fig.)	Extended Amount
1	Mobilization , move in of equipment and materials per APWA/ODOT Sec. 00210, complete.			
	1	LS	\$	\$
2	Work Zone Traffic Control, includes TCD, TCM and TCP per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00225 and 00225.90 (b), complete.			
	1	LS	\$	\$
3	Inlet Protection , per approved plans and APWA/ODOT Sec. 00280.16(d) Biofilter Bags, complete.			
	1	LS	\$	\$
PART 00300 – ROADWORK				
4	Asphalt Pavement Cutting for “T” Patch , per approved plans and APWA/ODOT Sec. 00310, 00405.48(c) and 00290.20(c) (Hazardous Waste), complete.			
	1100	LF	\$	\$
5	Removal of Structures and Obstructions , includes removal and proper disposal of existing AC, curb & gutter and sidewalk and saw cutting or other methods of cutting pavement, per approved plans and APWA/ODOT Sec. 00310.and 00291.20(c), (Hazardous Waste), complete.			
	1	LS	\$	\$
PART 00400 – DRAINAGE AND SEWERS				
6	48” Sanitary Sewer Manhole , per approved plans and, GPSD #301 and APWA /ODOT Sec. 00470. Includes manhole, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade, concrete collars and pipe connections, installed, complete.			
	2	EA	\$	\$
7	8” Sanitary Sewer Main, PVC 3034 , per approved plans and APWA /ODOT Sec. 00445. Includes pipe, trench excavation, bedding, backfill and connection to existing main, per GPSD #107 and APWA/ODOT Sec. 00405, installed, complete.			
	<u>52</u>	<u>LF</u>	\$	\$
7A	8” Sanitary Sewer Main, Class 52 Ductile Iron Pipe , per approved plans and APWA /ODOT Sec. 00445. Includes pipe, trench excavation, bedding, backfill and connection to existing main, per GPSD #107 and APWA/ODOT Sec. 00405, installed, complete.			
	<u>66</u>	<u>LF</u>	\$	\$
8	4” Ductile Iron Class 52 Sanitary Sewer Lateral , per approved plans, GPSD #304 and APWA/ODOT Sec. 00445. Includes, pipe, trench excavation, bedding, backfill, tee and cleanouts, per GPSD #107 and APWA/ODOT Sec. 00405, installed, complete to ROW.			
	<u>3</u>	<u>EA</u>	\$	\$

9	8" Sanitary Sewer Cleanout , per approved plans and APWA/ODOT Sec. 00445. Includes, cleanout, trench excavation, bedding, and backfill, per GPSD #303 and APWA/ODOT Sec. 00405, installed, complete.				
	1	EA	\$		\$
10	Remove Existing Sanitary Sewer and Waterline Creek Crossing , per approved plans and APWA/ODOT Sec. 00445. Includes trench excavation, bedding, and backfill, per GPSD #107 and APWA/ODOT Sec. 00405, removed, complete.				
	1	LS	\$		\$
PART 00700 – WEARING SURFACES					
11	Asphalt Pavement , <i>½" dense, Level 2 mix, 3" compacted thickness</i> , for "T" patch for trench restoration, per APWA/ODOT Sec. 00744 and GPSD #107-A, installed, complete.				
	60	TN	\$		\$
12	Concrete Curb & Gutter, Type "A" (Match Existing) , per approved plans, GPSD #102 and APWA/ODOT Sec. 00759, installed, complete.				
	45	LF	\$		\$
13	Concrete Sidewalk (Match Existing) , per approved plans, GPSD #106-A and APWA/ODOT Sec. 00759, installed, complete.				
	225	SF	\$		\$
PART 01100 – WATER SUPPLY SYSTEMS					
14	8" Water Pipe and Fittings, Class 52 Ductile Iron , per approved plans and, GPSD #304 and APWA /ODOT Sec. 00445. Includes pipe, fittings, valves, trench excavation, bedding and backfill per GPSD #107 and APWA/ODOT Sec. 00405, installed, complete.				
	410	LF	\$		\$
15	Potable Water Service Connection, 2 Inch and Smaller , per approved plans, GPSD #203 and APWA/ODOT Sec. 00405, installed, complete.				
	9	EA	\$		\$
PART 00200 – TEMPORARY FEATURES AND APPURTENANCES					\$
PART 00300 – ROADWORK					\$
PART 00400 – DRAINAGE AND SEWERS					\$
PART 00700 – WEARING SURFACES					\$
PART 01100 – WATER SUPPLY SYSTEMS					\$
SUM OF EXTENDED TOTALS					\$
CONTRACTOR SIGNATURE:					
DATE:					

END OF ADDENDUM NO. 1

ATTENDANCE LIST

Project Name/Number: 'C' Street Sanitary Sewer and Waterline Replacement / SE6156AWA4841 **Date:** 10/17/2013

Location: City Manager's Conference Room (10:00 a.m.)

Owner: City of Grants Pass **Engineer/Architect:** City of Grants Pass

Contracting Agency:

Contractor's Name:

MANDATORY PRE-BID X BID PRECONSTRUCTION

Name	Agency	Phone No./ Mobile No.	Email Address	Signature
1. Bob Bennett	Copeland Squad & General	541-476-476	bob@copeland-squad.com	[Signature]
2. Tom Smith	HGC Inc.	541-690-9149	tomsmith@hgcinc.net	[Signature]
3. Beth Morwick	Robco Inc.	541-476-2132	bjm@robcoinc.net	[Signature]
4. Frank McShannon	KO-TEP	541-776-6517	frank@kotec.com	[Signature]
5. BARRY PETERSON	BARRY PETERSON'S VERSATILE CONSTRUCTION	541-474-6007	barry@barry-peterson.com	[Signature]
6. Jessica Strick	Strick Construction LLC	541-476-1226	strick@strickconstruction.com	[Signature]
7. Bob L. Hargrove	CITY OF GP	541-669-1677		[Signature]
8. Scott Beauregard	COPELAND PAINTING	541-661-2387	scott@copelandpainting.com	[Signature]
9. [Name]	[Agency]	541-666-5000		[Signature]
10. Penny Ford	Avista	541-846-9114	avista@avista.com	[Signature]
11. Jake Schmidt	T.M.C.	958-9700	avista@avista.com	[Signature]
12. [Name]	[Agency]	761-6131		[Signature]
13. Nancy Murray	City of G.P.	450-6003		[Signature]
14. Kurt Clark	City of G.P.			[Signature]
15.				
16.				