

ADDENDUM NO. 2

to **CONTRACT DOCUMENTS** for

"D" & "E" & Dimmick 16" Water Main Abandonment

Project No. WA6167

Grants Pass, Oregon 97526

To All Planholders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction "D" & "E" & Dimmick 16" Water Main Abandonment; Project No. WA6167, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

1. ON THE CONSTRUCTION PLANS...

- *Change any references to "2" gate valve" to **"2½" gate valve"** as per Standard Drawing No.205*

2. IN THE CONTRACT DOCUMENTS...

Page 4 of 11 of the Bid Proposal, Bid Item No. 15 (2" Blow-Off Assembly)

- *Change "2" gate valve" to **"2½" gate valve"***

ATTACHED ARE THE FOLLOWING:

REVISED PAGES 3 THRU 4 OF THE BID PROPOSAL FOR REPLACING EXISTING PAGES 3 THRU 4 OF THE BID PROPOSAL AND MANDATORY PRE-BID MEETING ATTENDANCE LIST.

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 2 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE

HEREBY AGREED TO THIS _____ DAY OF _____ 2012.

Bidder's Name (Company)

BY: _____
(Signature)

BID SCHEDULE
“D” & “E” & Dimmick 16” Water Main Abandonment
WA6167

PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				
Item	Quantity	Unit	Unit Price (Fig.)	Extended Amount
1	Mobilization , move in of equipment and materials per APWA/ODOT Sec. 00210, complete.			
	1	LS	\$	\$
2	Work Zone Traffic Control includes TCD, TCM and TCP per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00225 and 00225.90(b), complete.			
	1	LS	\$	\$
3	Inlet Protection/Erosion Control , per approved plans and APWA/ODOT Sec. 00280.16(d), complete.			
	1	LS	\$	\$
PART 00300 – ROADWORK				
4	Asphalt Pavement Cutting, for “T” patch , per approved plans and APWA/ODOT Sec. 00310 and 00290.20(c), complete.			
	1550	LF	\$	\$
5	Removal of Structures and Obstructions , includes saw cutting, removal and proper disposal of existing AC and concrete, curb and gutter, sidewalks, driveway approaches and meter boxes, per approved plans and APWA/ODOT Sec. 00310 and 00290.20©, complete.			
	1	LS	\$	\$
PART 00400 – DRAINAGE AND SEWERS				
6	Sewer Lateral Conflict Adjustment , per approved plans and APWA/ODOT Sec. 00490, adjusted, complete.			
	1	EA	\$	\$
PART 00700 – WEARING SURFACES				
7	Asphalt Pavement , ½” Dense, Level 2 Mix, 3” Compacted Thickness, per APWA/ODOT Sec. 00744, for “T” patch for trench restoration, per GPSD 107. Installed, complete.			
	2250	SF	\$	\$
8	Concrete Curb & Gutter, Type “A” (Match Existing) , per approved plans, GPSD #102 and APWA/ODOT Sec. 00759. Includes asphalt patch back. Installed, complete.			
	70	LF	\$	\$
9	Concrete Residential Driveway , per approved plans, GPSD #104 and APWA/ODOT Sec. 00759. Includes 4” PVC sleeve. Installed, complete.			
	30	SF	\$	\$
10	Install 5’ Concrete Sidewalk , per approved plans, GPSD# 106A and APWA/ODOT Sec. 00759. Installed, complete.			
	135	SF	\$	\$
11	Remove and Relocate Stack Block Wall using Existing Blocks , behind new sidewalk.			
	1	LS	\$	\$

PART 01100 – WATER SUPPLY SYSTEMS				
12	8" Water Line, CL52 D.I.P. per approved plans and APWA/ODOT Sec. 01140. Includes all fittings and appurtenances, trench excavation, bedding and ¾"-0" backfill per GPSD #107 and APWA/ODOT Sec. 01140.40. Installed, complete.			
	520	LF	\$	\$
13	6" Water Line, CL52 D.I.P. per approved plans and APWA/ODOT Sec. 01140. Includes all fittings and appurtenances, trench excavation, bedding and ¾"-0" backfill per GPSD #107 and APWA/ODOT Sec. 01140.40. Installed, complete.			
	160	LF	\$	\$
14	6" FLG x MJ Gate Valve , per approved plans and APWA/ODOT Sec. 01140. Includes all necessary parts and appurtenances, trench excavation, bedding and backfill per GPSD #107 and APWA/ODOT Sec. 01140.40. Installed, complete. City to install Contractor provided valve.			
	1	EA	\$	\$
15	2" Blow-off Assembly , per approved plans, GPSD #205 (outlet detail through curb) and APWA/ODOT Sec. 01140. Includes 2½" gate valve , 8" MJ cap w/2" tap and all necessary appurtenances bringing galvanized pipe through curb, rodding and straddle blocks, trench excavation, bedding and backfill per GPSD #107 and APWA/ODOT Sec. 01140.40. Installed, complete.			
	3	EA	\$	\$
16	Air Release Valve , per approved plans, GPSD #206 and APWA/ODOT Sec. 01140. Includes all necessary parts and appurtenances. Installed, complete.			
	2	EA	\$	\$
17	Fire Hydrant, Short Lead , per approved plans, GPSD #202 and APWA/ODOT Sec. 01140. Includes connections, valve and all appurtenances and parts necessary. Installed, complete.			
	1	EA	\$	\$
18	1" Water Services , per approved plans, GPSD #203 & #219A and APWA/ODOT Sec. 01140. Includes connection to main, curb stop, corp. stop, 1" (IPS) Polyethylene class 200 psi line, #12 gauge blue coated solid wire, trench excavation, bedding and backfill per GPSD #107 and APWA/ODOT Sec. 01140.40. Installed, complete. City to supply meter box.			
	13	EA	\$	\$
19	Re-Plumbing to Individual Houses , as per Oregon Plumbing Specialty Code. Includes all necessary devices and fake rock over PRV. Installed, complete.			
	1	LS	\$	\$

ATTENDANCE LIST

Project Name/Number: 'D', 'E' & Dimmick 16" Water Main Abandonment / WA6167	Date: 12/13/2012
Location: Courtyard Conference Room (10:00 a.m.)	
Owner: City of Grants Pass	Engineer/Architect: City of Grants Pass
Contracting Agency:	
Contractor's Name:	
MANDATORY PRE-BID X BID PRECONSTRUCTION	

Name	Agency	Phone No./ Mobile No.	Email Address	Signature
1. Eric Peterson	BAVED, Inc.	541-913-9133	erick@baved.com	
2. Bob Caplan	CPT & CSG	476 4411		
3. Kenny Baine	Timber NT	501-4833		
4. Bob Leavel	Timber mfu	821-0068	Timbermfu227@gmail.com	
5. Bill O'Syune	Corix Water	541-680-2688	bill.osyune@corix.com	
6. Mark Chirrick	Condar Enterprises, Inc.	541-673-3268	mark@condar.com	
7. Dave Hengeman	Baizer Inc.	541-775-7553	daveh@baizerinc.com	
8. Tom Smith	H&C, Inc.	541-640-9149	tomsmithe@hgcinc.net	
9. Sean McFarland	PROSER	541-666-9777		
10. Dan Hadley	Pacific Plumbing	541-666-2322	pacificplumbing@pacnet.net	
11. Bob & Mable	CITY OF GRANTS PASS	541-660-1623	BOB.MABLE@CITYOFGRANTS.PASS.OREGON.GOV	
12. Mike Hsueh	Picot Brock Esq.	541-641-9238	MIKE@PICTROCK.COM	
13. Brady Peterson	Brady Peterson Const.	541-660-4973	Brady.Peterson1968@gmail.com	
14. Fred Sunner	City			
15. Brett Peterson	Grants Pass Construction	541-666-2742		
16. Dick Mieremetz	Pro-Once Construction	541-666-1471	m.mieremetz@pro-one.com	

Name	Agency	Phone No./ Mobile No.	Email Address	Signature
17. Kurt Clark	City of C.P.			<i>Kurt Clark</i>
18. Nancy Murray	City of HP			<i>Nancy Murray</i>
19.				
20.				
21.				
22.				
23.				
24.				
25.				
26.				
27.				
28.				
29.				
30.				
31.				
32.				
33.				
34.				
35.				
36.				
37.				
38.				
39.				
40.				

END OF ADDENDUM NO. 2