

**ADDENDUM NO. 1**

to **CONTRACT DOCUMENTS** for

Florer Drive Improvements  
Project No. TR4785  
Grants Pass, Oregon 97526

To All Planholders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction Florer Drive Improvements; Project No. TR4785, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

**1. ON THE CONSTRUCTION PLANS...**

**Sheet 2 of 4:**

- Sheet Keyed Note #12 – Change (16' Base) **to (20' Base)**

**2. IN THE CONTRACT DOCUMENTS...**

Change Bid Item #15, Concrete Residential Driveway Quantity from 150 SF **to 160 SF**

**ATTACHED IS THE FOLLOWING:**

**BID SCHEDULE PAGES 3-5 and MANDATORY PRE-BID ATTENDANCE LIST.**

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE

HEREBY AGREED TO THIS \_\_\_\_\_ DAY OF \_\_\_\_\_ 2013.

\_\_\_\_\_  
Bidder's Name (Company)

BY: \_\_\_\_\_  
(Signature)

**END OF ADDENDUM NO. 1**

## Bid Schedule

### Florer Drive Improvements TR4785


PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				
Item	Quantity	Unit	Unit Price (Fig.)	Extended Amount
1	<b>Mobilization</b> , move in of equipment and materials per APWA/ODOT Section 00210, complete.			
	1	LS	\$	\$
2	<b>Work Zone Traffic Control</b> , per approved plans, M.U.T.C.D., and APWA/ODOT Section 00225, complete.			
	1	LS	\$	\$
3	<b>Inlet Protection/Erosion Control</b> , per approved plans and APWA/ODOT Section 00280, complete.			
	1	LS	\$	\$
PART 00300 – ROADWORK				
4	<b>Removal of Structures and Obstructions</b> , per approved plans and APWA/ODOT Section 00310, complete.			
	1	LS	\$	\$
5	<b>General Earthwork (Excavation)</b> , per approved plans and APWA/ODOT Section 00330.			
	1	LS	\$	\$
PART 00400 – DRAINAGE AND SEWERS				
6	<b>4" Sanitary Sewer Lateral</b> per approved plans, GPSD #304 and APWA/ODOT Section 00445. Includes trench excavation, bedding and backfill, per APWA/ODOT Section 00405, installed, complete to back of new sidewalk.			
	1	EA	\$	\$
PART 00600 – BASES				
7	<b>Aggregate Base Course</b> , 8" thickness of ¾"-0 aggregate, compacted in place, per approved plans and APWA/ODOT Section 00640, 00641 and 02630. Installed complete.			
	200	TN	\$	\$
8	<b>Aggregate Base Course (Driveway)</b> , 6" thickness of ¾"-0 aggregate, compacted in place, per approved plans and APWA/ODOT Section 00640, 00641 and 02630. Installed complete.			
	85	TN	\$	\$

<b>PART 00700 – WEARING SURFACES</b>					
<b>9</b>	<b>Asphalt Pavement</b> , ½" dense, Level 2 mix, 3" compacted thickness, per APWA/ODOT Section 00744. Includes any minor valve or manhole adjustments. Installed complete.				
	85	TN	\$		\$
<b>10</b>	<b>Asphalt Pavement (Driveway)</b> , ½" dense, Level 2 mix, 2" compacted thickness, per APWA/ODOT Section 00744. Includes any minor valve or manhole adjustments. Installed complete.				
	30	TN	\$		\$
<b>11</b>	<b>Concrete Street Valley Gutter (Match Existing)</b> , per approved plans, GPSD #108 and APWA/ODOT Section 00759. Includes saw cutting. Installed, complete.				
	1	LS	\$		\$
<b>12</b>	<b>Concrete Curb &amp; Gutter, Type "A"</b> , per approved plans, GPSD #102 and APWA/ODOT Section 00759. Includes excavation, backfill and compaction. Installed complete.				
	270	LF	\$		\$
<b>13</b>	<b>Install 5' Concrete Sidewalk</b> , per approved plans, detail drawings, GPSD# 106A and APWA/ODOT Section 00759. Includes excavation, backfill, and compaction. Installed complete.				
	1260	SF	\$		\$
<b>14</b>	<b>Concrete Sidewalk Ramp with Truncated Domes (Yellow)</b> , per approved plans, GPSD #101 and APWA/ODOT Section 00759, (ERD755). Installed, complete.				
	2	EA	\$		\$
<b>15</b>	<b>Concrete Residential Driveway</b> , per approved plans, GPSD #104 and APWA/ODOT Section 00759. Includes 4" PVC sleeve.				
	160	SF	\$		\$
<b>PART 01100 – WATER SUPPLY SYSTEMS</b>					
<b>16</b>	<b>8" Water Line, CL52 D.I.P.</b> per approved plans and APWA/ODOT Section 01140. Includes all fittings and appurtenances, trench excavation, bedding and ¾"-0" backfill per GPSD #107 and APWA/ODOT Section 01140.40. Installed, complete.				
	185	LF	\$		\$
<b>17</b>	<b>8"x8"x8" Tapping Sleeve</b> , per approved plans and APWA/ODOT Section 01140. Includes thrust block, trench excavation, bedding and backfill per GPSD #107 and APWA/ODOT Section 01140.40. Installed, complete. City to test and perform tap.				
	1	EA	\$		\$
<b>18</b>	<b>12"x12"x8" Tapping Sleeve</b> , per approved plans and APWA/ODOT Section 01140. Includes thrust block, trench excavation, bedding and backfill per GPSD #107 and APWA/ODOT Section 01140.40. Installed, complete. City to test and perform tap.				
	1	EA	\$		\$
<b>19</b>	<b>8" FLG x MJ Gate Valve</b> , per approved plans and APWA/ODOT Section 01140. Includes all necessary parts and appurtenances, trench excavation, bedding and backfill per GPSD #107 and APWA/ODOT Section 01140.40. Installed, complete.				
	2	EA	\$		\$
<b>20</b>	<b>1" Water Services</b> , per approved plans, GPSD #203 & #219A and APWA/ODOT Section 01140. Includes connection to main, curb stop, corp. stop, 1" (IPS) Polyethylene class 200 psi line, #12 gauge blue coated solid wire, new meter box				

	(including lid with hinged peep), trench excavation, bedding and backfill per GPSD #107 and APWA/ODOT Section 01140.40. Installed, complete.			
	2	EA	\$	\$
<b>21</b>	<b>Fire Hydrant, Short Lead</b> , per approved plans, GPSD #202 and APWA/ODOT Section 01140. Includes connections, valve, all appurtenances and parts necessary. Installed complete.			
	1	EA	\$	\$
<b>PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL</b>				
<b>22</b>	<b>Install Fencing</b> , new 36" tall green vinyl chain link with green powder coated posts, rails and fittings behind Right of Way, per approved plans and APWA/ODOT Section 01050. Installed complete.			
	150	LF	\$	\$
<b>PART 00200 – TEMPORARY FEATURES AND APPURTENANCES</b>				
<b>PART 00300 – ROADWORK</b>				
<b>PART 00400 – DRAINAGE AND SEWERS</b>				
<b>PART 00600 – BASES</b>				
<b>PART 00700 – WEARING SURFACES</b>				
<b>PART 01100 – WATER SUPPLY SYSTEMS</b>				
<b>PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL</b>				
<b>SUM OF EXTENDED TOTALS:</b>				
				<b>Contractor Signature:</b>
				<b>Date:</b>

## ATTENDANCE LIST

Project Name/Number: Florer Drive Improvements / TR4785	Date: 2/07/2013
Location: Courtyard Conference Room (10:00 a.m.)	
Owner: City of Grants Pass	Engineer/Architect: Thornton Engineering, Inc.
Contracting Agency:	
Contractor's Name:	
MANDATORY PRE-BID <input checked="" type="checkbox"/> BID <input type="checkbox"/> PRECONSTRUCTION <input type="checkbox"/>	

Name	Agency	Phone No./ Mobile No.	Email Address	Signature
1. Robert Edwards	Stephen Stock Inc	541-476-7826	stock@stephenstock.com	
2. Brent Brachmann	Corporal Smith Scale	541-659-2289	brachmann@corporalsmith.com	
3. Ryan Rappaport	Rebus, Inc.	541-476-2132	ryan@rebusinc.net	
4. Ryan Branson	Par-A-Dice Court.	541-326-9318	ryan@paradice.com	
5. Jake Smith	Immer MTH. Const.	951-877-010	smith@immermth.com	
6. Bob Bennett	Corporal Smith Scale	541-476-7826	bennett@corporalsmith.com	
7. Steve Koble	W-Cover	541-769-1111	skoble@wcover.com	
8. Sam Crimi	DownTown De Boston	541-641-4885	crimi@downtownde.com	
9. Barry Peterson	Barry Peterson's	541-476-6007	barry@barrypeterson.com	
10. Nancy Murray	City of G.P.	450-6063	nancy@murray.com	
11. Jim Decker	City of G.P.	450-6093	jim@decker.com	
12. Bob & Dianne	Extra Water & Sewer	450-6115	bob@extrawater.com	
13. Don Aslund	Corporal Smith Const.	660-3502	don@corporalsmith.com	
14. Kurt Clark	City of G.P.		kurt@cityofgp.com	
15.				
16.				