

ADDENDUM NO. 1

to **CONTRACT DOCUMENTS** for

Josephine Street and "L" Street Reconstruction
Project No. TR6157
Grants Pass, Oregon 97526

To All Plan Holders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of the Josephine Street and "L" Street Reconstruction; Project No. TR6157, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

1. ON THE CONSTRUCTION PLANS...

- **NA**

2. IN THE CONTRACT DOCUMENTS...

- In the Bid Schedule, **Change Bid Item #6** from "Includes hand excavation around existing redwood trees" to **"Including but not limited to"** hand excavation around existing redwood trees.
- In the Bid Schedule, **Change Bid Item #7 Quantity** from "3 Each" Std. 48" Eccentric Storm Sewer Manholes to **"4 Each" Std. 48" Eccentric Storm Sewer Manholes**
- In the Bid Schedule, **Delete Bid Item #23 "Fire Hydrant, Short Lead"**

ATTACHED ARE REVISED BID SCHEDULE PAGES OF THE BID PROPOSAL. PLEASE USE THESE REPLACEMENT PAGES WHEN SUBMITTING YOUR BID. ALSO INCLUDED IS THE MANDATORY PRE-BID MEETING ATTENDANCE LIST.

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE

HEREBY AGREED TO THIS ____ DAY OF _____ 2013.

Bidder's Name (Company)

BY: _____
(Signature)

BID SCHEDULE
Josephine Street and "L" Street Reconstruction
TR6157

PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				
Item	Quantity	Unit	Unit Price (Fig.)	Extended Amount
1	Mobilization , move in of equipment and materials per APWA/ODOT Sec. 00210, complete.			
	1	LS	\$	\$
2	Work Zone Traffic Control, includes TCD, TCM and TCP per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00225 and 00225.90 (b), complete.			
	1	LS	\$	\$
3	Inlet Protection , per approved plans and APWA/ODOT Sec. 00280.16(d) Biofilter Bags, complete.			
	1	LS	\$	\$
PART 00300 – ROADWORK				
4	Removal of Structures and Obstructions , includes fence removal, removal and proper disposal of existing pipe, AC, curb & gutter and sidewalk and saw cutting or other methods of cutting pavement, per approved plans and APWA/ODOT Sec. 00310.and 00291.20(c), (Hazardous Waste), complete.			
	1	LS	\$	\$
5	Adjust Water Meter Boxes , per approved plans and APWA/ODOT Sec. 00490.48.			
	15	EA	\$	\$
6	General Earthwork (Excavation) , per approved plans and APWA/ODOT Section 00330. Including but not limited to hand excavation around existing redwood trees.			
	1	LS	\$	\$
PART 00400 – DRAINAGE AND SEWERS				
7	Std. 48" Eccentric Storm Sewer Manhole , per approved plans and, GPSD #301 and APWA /ODOT Sec. 00470. Includes manhole, excavation, bedding and compacted backfill per APWA/ODOT Sec. 00405, adjustment to finish grade, concrete collars and pipe connections, installed, complete.			
	4	EA	\$	\$
8	Install 12" Storm Drain Pipe, HDPE , per approved plans and APWA/ODOT Sec. 00445. Includes connection to storm drain system and plugging existing storm drain, trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	726	LF	\$	\$
9	Install 12" Storm Drain Pipe, Class V Concrete , per approved plans and APWA/ODOT Sec. 00445. Includes connection to storm drain system, trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	7	LF	\$	\$





10	Concrete Inlet, Type "B" , per GPSD #112, approved plans and APWA/ODOT Sec. 00470. Includes excavation, backfill and all pipe connections. Installed, complete.
	5 EA \$ \$
11	Loose Riprap Class 100 , per approved plans and APWA/ODOT Sec. 00390, installed complete.
	12 TN \$ \$
PART 00600 – BASES	
12	Aggregate Base Course , 8" thickness of ¾"-0 aggregate, compacted in place, per approved plans and APWA/ODOT Section 00640, 00641 and 02630. Installed complete.
	1420 TN \$ \$
13	Aggregate Base Course (Driveway) , Varying thickness of ¾"-0 aggregate, compacted in place, per approved plans and APWA/ODOT Section 00640, 00641 and 02630. Installed complete.
	40 TN \$ \$
PART 00700 – WEARING SURFACES	
14	Asphalt Pavement , ½" dense, Level 2 mix, 3" compacted thickness, per APWA/ODOT Section 00744. Includes any minor valve or manhole adjustments. Installed complete.
	550 TN \$ \$
15	Asphalt Pavement (Driveway) , ½" dense, Level 2 mix, 2" compacted thickness, per APWA/ODOT Section 00744. Includes any minor valve or manhole adjustments. Installed complete.
	60 TN \$ \$
16	Concrete Curb & Gutter, Type "A" (Match Existing) , per approved plans, GPSD #102 and APWA/ODOT Sec. 00759, installed, complete.
	1470 LF \$ \$
17	Concrete Sidewalk (Match Existing) , per approved plans, GPSD #106-A and APWA/ODOT Sec. 00759, installed, complete.
	5940 SF \$ \$
18	Concrete Sidewalk Ramp with Truncated Domes (Yellow) , per approved plans, GPSD #101 and APWA/ODOT Section 00759, (ERD755). Installed, complete.
	5 EA \$ \$
19	Concrete Residential Driveway , per approved plans, GPSD #104-A and APWA/ODOT Section 00759. Includes 4" PVC sleeve.
	1755 SF \$ \$
20	Concrete Commercial Driveway , per approved plans, GPSD #105-A and APWA/ODOT Section 00759. Includes 4" PVC sleeve.
	990 SF \$ \$
21	Concrete Street Valley Gutter (Match Existing) , per approved plans, GPSD #108 and APWA/ODOT Section 00759. Includes saw cutting. Installed, complete.
	1 LS \$ \$

PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL				
22	Install Fencing , new 36" tall green vinyl chain link with green powder coated posts, rails and fittings behind Right of Way, per approved plans and APWA/ODOT Section 01050. Installed complete.			
	105	LF	\$	\$
PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				\$
PART 00300 – ROADWORK				\$
PART 00400 – DRAINAGE AND SEWERS				\$
PART 00600 – BASES				\$
PART 00700 – WEARING SURFACES				\$
PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL				\$
SUM OF EXTENDED TOTALS				\$
CONTRACTOR SIGNATURE:				
DATE:				

END OF ADDENDUM NO. 1

ATTENDANCE LIST

Project Name/Number: Josephine Street and "L" Street Reconstruction/TR6157		Date: 07/31/2013
Location: Courtyard Conference Room (10:00 a.m.)		
Owner: City of Grants Pass	Engineer/Architect: City of Grants Pass	
Contracting Agency:		
Contractor's Name:		
MANDATORY PRE-BID <input checked="" type="checkbox"/> BID <input type="checkbox"/> PRECONSTRUCTION <input type="checkbox"/>		

Name	Agency	Phone No./ Mobile No.	Email Address	Signature
1. Jay Moser	Moser PAVING	541-245-2434 660-0516	cj@moser-paving.com	
2. Rob Ferrara	Timber mtn	541-821-0068		
3. Dick Rogers	Pine Acres Concrete	660-1491	ronmeyer@pac.com	
4. Bob Campbell	Capland Paving	660-5902		
Jennifer Ausland	Capeland Sandland	660-7168	Jennifer@capelandpaving.com	
6. Cody Tibbitts	Knife River	701-4127	dave.ross@kniferiver.edu	
7. Frank McElhenny	KOGAP	776-6527	Sharon@Kogapa.com	
8. Tom Smith	HGC, Inc.	541-610-9149	tomsmith@hginc.net	
9. Eric Rosenbaum	Rosen, Inc.	476-2132	eric@roseninc.net	
10. Nancy Murny	City of G.P.	450-6063	nmurny@grantspass.oregon.gov	
11. Kurt Clark	City of G.P.			
12. Fred Saunders	City of G.P.			
13.				
14.				
15.				
16.				