

## **ADDENDUM NO. 1**

to **CONTRACT DOCUMENTS** for

Savage Street Bridge  
Project No. TR6165  
Grants Pass, Oregon

To All Plan Holders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of the Savage Street Bridge, Project No. TR6165, as fully and completely as if the same were fully set forth therein:

### **1. GENERAL CLARIFICATIONS:**

- **Anticipated sanitary sewer flows:**
  - The sanitary sewer flows are anticipated to be one-third (1/3) of full pipe capacity during summer months. This equates to approximately (1.9 cfs (cubic feet per second) or 860 gpm (gallons per minute)).
- **Anticipated creek flows:**
  - The anticipated normal flow within Gilbert Creek (outside of a storm event) is approximately 5 cfs (cubic feet per second) or 2,250 gpm (gallons per minute)) during summer months.
- **Structural Inspection of Structures within the Project Area:**
  - The City of Grants Pass will inspect all structures within the project area for any existing structural and non-structural damage prior to the commencement of pile driving activities. Any and all discovered damage will be documented. A post-pile driving structural inspection will then be conducted by the City of Grants Pass to document any changes. If any damage is discovered, the City of Grants Pass will evaluate the damage on a case by case basis.
  - The Contractor will not be liable for any structural damage to existing structures within the project area that was caused as a direct result of the dynamic energy associated with pile driving activities that takes places in the presence of the Engineer of Record and the City of Grants Pass.
- **Storage of Materials within Right-of-Way:**
  - Construction materials and equipment may be stored within the Savage Street Right-of-Way as long as a clear lane and access is maintained to all private residences on the street.
- **Prequalification of Subcontractors:**
  - All first-tier listed subcontractors for the Awarded Bidder shall obtain City of Grants Pass Prequalification prior to issuance of Notice to Proceed for the project.

**2. SAVAGE STREET BRIDGE – PLANS:**

- **Drawing C1.11:**
  - Delete Construction Note 38 and all references in its entirety: “APPLY PAINT 4” WIDE YELLOW BROKEN LINE PER CITY OF GRANTS PASS STANDARDS.”
- **Drawing C1.21:**
  - Revise Construction Note 35 to read as follows: “Construct storm outfall. Armor outfall slope with **CLASS 200 RIPRAP** to a minimum depth of 24” Coordinate riprap placement with City Inspector prior to placement.”
- **Drawing S3.1 – Section 1:**
  - Delete note in its entirety: “WARRANTED SPRAY WATERPROOF MEMBRANE”.

**3. SAVAGE STREET BRIDGE – SPECIAL PROVISIONS:**

- **Page 2 – Table of Contents:**
  - Delete: “SECTION 00591 – SPRAY WATERPROOFING MEMBRANE....34”.
- **Page 5 – Professional of Record Certification(s):**
  - Delete: “00591”.
- **Page 34 – Section 00591 – Spray Waterproofing Membrane:**
  - Delete Section in its entirety.

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE HEREBY AGREED TO

THIS \_\_\_\_ DAY OF \_\_\_\_\_ 2016.

\_\_\_\_\_  
Bidder's Name (Company)

BY:

\_\_\_\_\_  
(Signature)

**END OF ADDENDUM NO. 1**