

ADDENDUM NO. 1

to **CONTRACT DOCUMENTS** for

Baker Park Parking Lot Reconstruction

Project No. LB6189

Grants Pass, Oregon 97526

To All Plan Holders:

The following changes, additions, and/or deletions are hereby made a part of the Contract Documents for the construction of the Baker Park Parking Lot Reconstruction, Project No. LB6189, Grants Pass, Oregon, as fully and completely as if the same were fully set forth therein:

1. IN THE CONTRACT DOCUMENTS...

Bid Proposal - Bid Schedule: - The following bid items have been revised or added.

8	Asphalt Pavement Cutting , per approved plans and APWA/ODOT Section 0000310 and City pavement cut policy.			
	846	LF	\$	\$
9	Rock Riprap, Class 50 , per approved plans, installed complete.			
	10		\$	\$

Note: Original bid item number 8, has been removed completely. Bid item 9 is added to bid schedule. Bid numbers 8-27 have been renumbered.

CLARIFICATIONS...

Revised Bid Schedule is THREE pages.

- **BID SCHEDULE ITEM 5 - REMOVAL OF STRUCTURES AND OBSTRUCTIONS INCLUDES ALL PAVEMENT REMOVAL, SAW CUTTING, GRINDING, ETC., NOT SPECIFIED ELSEWHERE IN THIS BID SCHEDULE.**
- **BID SCHEDULE ITEM 6 - GENERAL EARTHWORK (EXCAVATION) DELETE THE SECOND SENTENCE "ALSO INCLUDED IS AIR/PNEUMATIC ...".**
- **BID SCHEDULE ITEM 8 - ASPHALT PAVEMENT CUTTING - DELETE THIS ITEM.**

-
- **BID SCHEDULE ITEM 10 - INSTALL NEW WATER QUALITY FEATURE INCLUDES THE CONSTRUCTION OF THE BIOSWALE IN ITS ENTIRETY IN CONFORMANCE WITH APWA/ODOT SEC. 1030 AND 1040, AND INCLUDES THREE ALTERNATE PLANTING SCHEDULES AS SPECIFIED ON SHEET 5 OF 7, TABLE A-1.**
 - **BID SCHEDULE ITEM 13 - ASPHALT PAVEMENT PATCH INCLUDES OTHER METHODS OF PAVEMENT REMOVAL, INCLUDING GRINDING**
 - **THE CONTRACTOR IS NOT REQUIRED TO SUBMIT A SITE SPECIFIC POLLUTION CONTROL PLAN, BUT THE CONTRACTOR SHALL PERFORM ALL OTHER REQUIREMENTS OF APWA/ODOT SECTION 290. THIS WORK IS CONSIDERED INCIDENTAL TO THE PROJECT.**
 - **ADD ITEM: ROCK RIPRAP, CLASS 50, 10 TONS, INSTALLED COMPLETE**
 - **SEE BELOW FOR ATTACHED SAMPLE OF ARCHEOLOGICAL INADVERTANT DISCOVERY PLAN (IDP).**

ATTACHED ARE THE FOLLOWING:

- **REVISED PAGES OF THE BID SCHEDULE (3 PAGES)**
- **PLEASE NOTE THAT BID ITEMS HAVE BEEN REVISED, AND THE ITEMS 8- 27 HAVE BEEN RENUMBERED**

PLEASE USE THESE REPLACEMENT PAGES WHEN SUBMITTING YOUR BID.

All Bidders shall acknowledge receipt and acceptance of this Addendum No. 1 by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum will be considered irregular and may not be accepted.

RECEIPT OF THIS ADDENDUM IS ACKNOWLEDGED AND CONDITIONS ARE HEREBY

AGREED TO THIS _____ DAY OF _____ 2022.

Bidder's Name (Company)

BY: _____
(Signature)

END OF ADDENDUM NO. 1

BID SCHEDULE
Baker Park Parking Lot Reconstruction
LB6189

PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				
Item	Quantity	Unit	Unit Price (Fig.)	Extended Amount
1	Mobilization , move in of equipment and materials per APWA/ODOT Sec. 00210, complete.			
	1	LS	\$	\$
2	Work Zone Traffic Control, includes TCD, TCM and TCP per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00225 and 00225.90 (b), complete.			
	1	LS	\$	\$
3	Erosion & Sediment Control , per approved plans and APWA/ODOT Sec. 00280.00 Inlet Protection, Dust Control, Sediment Fence, Biofilter Bags, installed complete.			
	1	LS	\$	\$
4	Construction Staking , lay out and set construction stakes and marks to establish the lines, grades, and slopes necessary for project completion, per Special Provisions Sec. 00150.15 (c).			
	1	LS	\$	\$
PART 00300 – ROADWORK				
5	Removal of Structures and Obstructions , includes removal and proper disposal of trees, stumps, existing pipe, AC, curb & gutter and sidewalk and saw cutting or other methods of cutting pavement, per approved plans and APWA/ODOT Sec. 00310.and 00291.20(c), (Hazardous Waste), complete.			
	1	LS	\$	\$
6	General Earthwork (Excavation) , per approved plans and APWA/ODOT Section 00330..			
	1	LS	\$	\$
7	Subgrade Geotextile , per approved plans and APWA/ODOT Sec. 00350. Installed, complete.			
	468	SY	\$	\$
PART 00400 – DRAINAGE AND SEWERS				
8	Install 8” Storm Drain Pipe, PVC 3034 , per approved plans and APWA/ODOT Sec. 00445. Includes trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.			
	5	LF	\$	\$
9	Rock Riprap, Class 50 , per approved plans, installed complete.			
	10	TN	\$	\$

10	Install New Water Quality Feature , per approved plans, and APWA/ODOT Sec. 00445. Installed complete.			
	1	LS	\$	\$
11	Catch Basin , per approved plans and APWA/ODOT Sec. 00470. Includes excavation, backfill and all pipe connections. Installed complete.			
	1	EA	\$	\$
PART 00600 – BASES				
12	Aggregate Base Course , Varying thickness of ¾"-0 aggregate, compacted in place, per approved plans and APWA/ODOT Section 00640, 00641 and 02630. Installed complete for roadway construction.			
	193	TN	\$	\$
PART 00700 – WEARING SURFACES				
13	Asphalt Pavement Patch , ½" dense, Level 2 mix, 3" compacted thickness, per APWA/ODOT Section 00744. Includes sawcutting, pavement removal, excavation, base rock, any minor valve or manhole adjustments. Installed complete.			
	90	TN	\$	\$
14	Concrete Curb, Type "C" (Match Existing) , per approved plans, GP700 and APWA/ODOT Sec. 00759. Includes sawcutting, curb removal, curb openings per detail, excavation, base rock, installed complete.			
	204	LF	\$	\$
15	Concrete Sidewalk Ramp with Truncated Domes (Yellow) , per approved plans, GP756 and APWA/ODOT Section 00759, (ERD755). Includes excavation, base rock, concrete flatwork, truncated domes, extra thickness and rebar per plans, installed complete.			
	233	SF	\$	\$
16	Concrete Sidewalk , per approved plans and APWA/ODOT Sec. 00759. Includes excavation, base rock, installed complete.			
	155	SF	\$	\$
17	Concrete Curb and Gutter, Type "A" , per approved plans, GP700 and APWA/ODOT Sec. 00759. Includes excavation, base rock, installed complete.			
	146	LF	\$	\$
18	Seal Coat Asphalt Parking Lot , per approved plans, APWA/ODOT Sec. 00706, installed, complete.			
	40,125	SF	\$	\$
PART 00800 – PERMANENT TRAFFIC SAFETY AND GUIDANCE SYSTEM				
19	4" White Striping , sprayed, surface, non-profiled. Per TM500 (W), approved plans, and APWA/ODOT Sec. 00865. Installed, complete.			
	1,370	LF	\$	\$
20	12" White Striping , sprayed, surface, non-profiled. Per TM503 (S), approved plans, and APWA/ODOT Sec. 00865. Installed, complete.			
	30	LF	\$	\$

21	White Arrows , sprayed, surface, non-profiled. Per TM501 (SA), approved plans, and APWA/ODOT Sec. 00865. Installed, complete.			
	10	EA	\$	\$
22	Handicap Symbol , sprayed, surface, non-profiled. Per TM500 (HC), approved plans, and APWA/ODOT Sec. 00865. Installed, complete.			
	4	EA	\$	\$
PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL				
23	Landscape Restoration , restore existing landscaping, including, but not limited to imported topsoil placement, reseeding of disturbed areas and irrigation repair, per approved plans and APWA/ODOT Section 01030, Section 01040 and Section 01120. Installed complete.			
	1	LS	\$	\$
24	Parking Lot Lighting , per approved plans. Includes electrical research and design, foundation, pole, light, wiring and conduit. Installed complete.			
	2	EA	\$	\$
25	New Stair Railing , per approved plans. Installed complete.			
	1	LS	\$	\$
26	Tree Protection Fencing , per approved plans and tree protection plan specifications. Installed complete.			
	1	LS	\$	\$
27	Pneumatic Air Excavation , per approved plans and pneumatic air excavation specifications, installed complete.			
	1	LS	\$	\$
PART 00200 – TEMPORARY FEATURES AND APPURTENANCES				\$
PART 00300 – ROADWORK				\$
PART 00400 – DRAINAGE AND SEWERS				\$
PART 00600 – BASES				\$
PART 00700 – WEARING SURFACES				\$
PART 00800– PERMANENT TRAFFIC SAFETY AND GUIDANCE SYSTEM				\$
PART 01000 – RIGHT OF WAY DEVELOPMENT AND CONTROL				\$
SUM OF EXTENDED TOTALS				\$
CONTRACTOR SIGNATURE:				
DATE:				