



City of Grants Pass
"M" STREET (7TH STREET TO 9TH STREET) SEWER REHABILITATION
 Project No. SE6375.400073

BID SUMMARY

		Bidder		City of Grants Pass (Engineers Estimate)		Timber Mountain Construction	
		Address CSZ Phone		101 NW "A" Street Grants Pass, OR 97526 (541) 450-6060 NA NA		PO Box 930 Grants Pass, OR 97537 (541) 956-8700 NA 10%	
		Addendums No. 1 Acknowledged Bid Security				1	
Item No.	Description of Item	Quantity	Unit	Unit Price	Amount	Unit Price	Amount
1	Mobilization , move in of equipment and materials per APWA/ODOT Sec. 00210, complete.	1	l.s.	\$17,000.00	\$17,000.00	\$16,400.00	\$16,400.00
2	Flagging Hours , APWA/ODOT Sec. 00223.90 (a)	620	hrs	\$57.00	\$35,340.00	\$57.00	\$35,340.00
3	Work Zone Traffic Control, includes TCD, TCM and TCP per approved plans, M.U.T.C.D., and APWA/ODOT Sec. 00223 and 00223.90 (b), complete.	1	l.s.	\$3,000.00	\$3,000.00	\$6,892.00	\$6,892.00
4	Traffic Control Supervisor , TCS will oversee ALL traffic control operations on a daily basis and will be the direct contact for discussion and implementation of any traffic control issues and/or concerns for the duration of the project, per approved plans and APWA/ODOT Sec. 00223.31	1	l.s.	\$20,000.00	\$20,000.00	\$4,372.00	\$4,372.00
5	Erosion & Sediment Control , per approved plans and APWA/ODOT Sec. 00280.00 Inlet Protection, Dust Control, Sediment Fence, Biofilter Bags, installed complete.	1	l.s.	\$500.00	\$500.00	\$650.00	\$650.00
6	Removal of Structures and Obstructions , includes removal and proper disposal of existing pipe, AC, curb & gutter and sidewalk and saw cutting or other methods of cutting pavement, per approved plans and APWA/ODOT Sec. 00310 and 00290.20(c), (Hazardous Waste), complete.	1	l.s.	\$2,000.00	\$2,000.00	\$5,363.00	\$5,363.00
7	Asphalt Pavement Cutting for "T" patch , per approved plans and APWA/ODOT Section 00310 and City pavement cut policy.	72	l.f.	\$3.00	\$216.00	\$10.00	\$720.00
8	Install 12" Sanitary Sewer Pipe, PVC Install 12" Sanitary Sewer Main, PVC 3034 , per approved plans, per GP300 and APWA/ODOT Sec. 00445. Includes pipe, trench excavation, bedding and compacted backfill per APWA/ODOT Sec.00405, installed complete.	20	l.f.	\$250.00	\$5,000.00	\$936.00	\$18,720.00
9	Install 12" Sanitary Sewer Main, CIPP Lining , per approved plans, per APWA/ODOT Sec. 00412. Includes furnishing and placing all materials and furnishing all equipment, labor and incidentals to rehabilitate existing 12" Sanitary Sewer Main using trenchless methods per APWA/ODOT Sec.00412, installed complete.	720	l.f.	\$230.00	\$165,600.00	\$135.00	\$97,200.00
10	4" Sanitary Sewer Lateral , per approved plans and APWA/ODOT Sec. 00445. Includes, pipe, trench excavation, bedding and backfill, per GP300 and APWA/ODOT Sec. 00405, installed, complete.	1	ea.	\$2,160.00	\$2,160.00	\$4,836.00	\$4,836.00
11	Reinstate Sanitary Sewer Lateral After CIPP Lining , per approved plans, and APWA/ODOT Sec. 00411. Includes all connections to existing sanitary sewer lateral pipe, installed complete.	8	ea.	\$2,000.00	\$16,000.00	\$910.00	\$7,280.00
12	Asphalt Pavement Patch , ½" dense, Level 2 mix, 4" compacted thickness, per APWA/ODOT Section 00744. Includes sawcutting, pavement removal, excavation, base rock, any minor valve or manhole adjustments. Installed complete.	4	ton	\$225.00	\$900.00	\$1,024.00	\$4,096.00
"M" Street (7th Street to 9th Street) Sewer rehabilitation (1-12)				\$267,716.00		\$201,869.00	

BIDS WERE OPENED ON 12/15/2022 AT 3:05 PM IN THE CITY OF GRANTS PASS CITY MANAGER'S CONFERENCE ROOM.